



3250 Linebaugh Rd.
 Xenia, OH 45385
 Telephone (800) 762-0040
 FAX (937) 879-8425

**CEMENT
MILL
TEST**

Cement Identified as: **Type III** **Date:** **03/30/20**
Production Dates: **February, 2020** **Silo:** **3**

STANDARD CHEMICAL REQUIREMENTS (ASTM C 114)	SPECIFICATIONS	ASTM C 150 TYPE III	AASHTO M85 Type III	RESULTS
Silicon Dioxide (SiO ₂), %		----		18.9
Aluminum Oxide (Al ₂ O ₃), %		----		4.5
Ferric Oxide (Fe ₂ O ₃), %		----		3.2
Calcium Oxide (CaO), %		----		62.1
Magnesium Oxide (MgO), %	Maximum	6.0	6.0	4.6
Sulfur Trioxide (SO ₃), % ^A	Maximum	3.5	3.5	4.2
Loss on Ignition (LOI), %	Maximum	3.5	3.5	1.9
Insoluble Residue, %	Maximum	1.50	1.5	0.42
Free Calcium Oxide, %				0.7
Alkalies (Na ₂ O equivalent), %		----		0.78
Tricalcium Silicate (C ₃ S), Potential %		----		63
Dicalcium Silicate (C ₂ S), Potential %		----		7
Tricalcium Aluminate (C ₃ A), Potential %	Maximum	15	15	6
Tetracalcium Aluminoferrite (C ₄ AF), Potential %		----		10
CO ₂ , %				1.1
Limestone, %	Maximum	5.0	5.0	2.5
CaCO ₃ in Limestone, %	Minimum	70	70	97
PHYSICAL REQUIREMENTS				
(ASTM C 204) Blaine Fineness, m ² /kg		----		634
(ASTM C 191) Time of Setting (Vicat)				
Initial Set, minutes	Minimum	45	45	76
Final Set, minutes	Maximum	375	375	153
(ASTM C 185) Air Content, %	Maximum	12	12	7
(ASTM C 151) Autoclave Expansion, %	Maximum	0.80	0.80	0.13
(ASTM C 1038) Expansion in Water, %	Maximum	0.02	0.02	0.008
(ASTM C 187) Normal Consistency, %		----		28.9
(ASTM C 109) Compressive Strength, psi (Mpa)				
1 Day	Minimum	1740 (12.0)	1740 (12.0)	4440 (30.6)
3 Day	Minimum	3480 (24.0)	3480 (24.0)	5622 (38.8)
7 Day		----		6198 (42.7)
28 Day		----		6988 (48.2)

^A Per ASTM C150 Table 1 footnote D

We hereby certify that this cement conforms to all of the standard requirements for portland cement in the above specification for the type specified.

By: Rusty Strader

Physical Testing completed by: DG, MS
 Chemical Testing completed by: TA, NC, JD, NM

Rusty Strader
 Quality Control Manager
 Fairborn Cement Company



3250 Linebaugh Rd.
 Xenia, OH 45385
 Telephone (800) 762-0040
 FAX (937) 879-8425

**CEMENT
MILL
TEST**

Cement Identified as:	Type III	Date: 03/30/20
Production Period:	February, 2020	Silo: 3

Additional Data

	Inorganic Processing Addition Data	Limestone
Type	Baghouse Dust	---
Amount (%)	0.0	2.5
SiO2 (%)	11.7	0.9
Al2O3 (%)	3.0	0.6
Fe2O3 (%)	1.6	0.6
CaO (%)	39.1	45.9
SO3 (%)	0.3	0.2

Base cement Phase Composition

C3S (%)	58
C2S (%)	10
C3A (%)	6
C4AF (%)	10

We hereby certify that this cement conforms to all of the standard requirements for portland cement in the above specification for the type specified.

By: *Rusty Strader*

Rusty Strader
 Quality Control Manager
 Fairborn Cement Company